

ACI 302.1R-15

Guide to Concrete Floor and Slab Construction

Reported by ACI Committee 302



American Concrete Institute
Always advancing



Guide to Concrete Floor and Slab Construction

Copyright by the American Concrete Institute, Farmington Hills, MI. All rights reserved. This material may not be reproduced or copied, in whole or part, in any printed, mechanical, electronic, film, or other distribution and storage media, without the written consent of ACI.

The technical committees responsible for ACI committee reports and standards strive to avoid ambiguities, omissions, and errors in these documents. In spite of these efforts, the users of ACI documents occasionally find information or requirements that may be subject to more than one interpretation or may be incomplete or incorrect. Users who have suggestions for the improvement of ACI documents are requested to contact ACI via the errata website at <http://concrete.org/Publications/DocumentErrata.aspx>. Proper use of this document includes periodically checking for errata for the most up-to-date revisions.

ACI committee documents are intended for the use of individuals who are competent to evaluate the significance and limitations of its content and recommendations and who will accept responsibility for the application of the material it contains. Individuals who use this publication in any way assume all risk and accept total responsibility for the application and use of this information.

All information in this publication is provided “as is” without warranty of any kind, either express or implied, including but not limited to, the implied warranties of merchantability, fitness for a particular purpose or non-infringement.

ACI and its members disclaim liability for damages of any kind, including any special, indirect, incidental, or consequential damages, including without limitation, lost revenues or lost profits, which may result from the use of this publication.

It is the responsibility of the user of this document to establish health and safety practices appropriate to the specific circumstances involved with its use. ACI does not make any representations with regard to health and safety issues and the use of this document. The user must determine the applicability of all regulatory limitations before applying the document and must comply with all applicable laws and regulations, including but not limited to, United States Occupational Safety and Health Administration (OSHA) health and safety standards.

Participation by governmental representatives in the work of the American Concrete Institute and in the development of Institute standards does not constitute governmental endorsement of ACI or the standards that it develops.

Order information: ACI documents are available in print, by download, on CD-ROM, through electronic subscription, or reprint and may be obtained by contacting ACI.

Most ACI standards and committee reports are gathered together in the annually revised ACI Manual of Concrete Practice (MCP).

American Concrete Institute
38800 Country Club Drive
Farmington Hills, MI 48331
Phone: +1.248.848.3700
Fax: +1.248.848.3701

www.concrete.org

Guide to Concrete Floor and Slab Construction

Reported by Committee 302

Joseph F. Neuber Jr., Chair
Patrick J. Harrison, Vice Chair

Russell E. Neudeck, Secretary

Dennis C. Ahal
Bryan M. Birdwell
Peter A. Craig
Allen Face
C. Rick Felder
Edward B. Finkel
Barry E. Foreman
Greg K. Fricks
Terry J. Fricks

Jerry A. Holland
Philip S. Kopf
Steve R. Lloyd, Sr.
Kevin A. MacDonald
Arthur W. McKinney
Donald M. McPhee
Scott C. Metzger
Jeffrey S. Miller
Scott L. Niemitalo

Nigel K. Parkes
William S. Phelan
Tim H. Robinson
John W. Rohrer
Paul A. Rouis, III
Domenick Thomas Ruttura
Bruce A. Suprenant
Scott M. Tarr
Consulting Members

Carl Bimel*
Michael A. Clark
William C. Panarese
Brian J. Pashina
Boyd C. Ringo*

*Deceased

The quality of a concrete floor or slab is highly dependent on achieving a hard and durable surface that is flat, relatively free of cracks, and at the proper grade and elevation. Properties of the surface are determined by the mixture proportions and the quality of the concreting and jointing operations. The timing of concreting operations—especially finishing, jointing, and curing—is critical. Failure to address this issue can contribute to undesirable characteristics in the wearing surface such as cracking, low resistance to wear, dusting, scaling, high or low spots, poor drainage, and increasing the potential for curling.

Concrete floor slabs employing portland cement, regardless of slump, will start to experience a reduction in volume as soon as they are placed. This phenomenon will continue as long as any water, heat, or both, is being released to the surroundings. Moreover, because the drying and cooling rates at the top and bottom of the slab are not the same, the shrinkage will vary throughout the depth, causing the as-cast shape to be distorted and reduced in volume.

This guide contains recommendations for controlling random cracking and edge curling caused by the concrete's normal volume change. Application of present technology permits only a reduction in cracking and curling, not elimination. Even with the best floor designs and proper construction, it is unrealistic to expect completely crack- and curl-free floors. Consequently, every owner should be advised by both the designer and contractor that it is completely normal to expect some amount of cracking and curling

on every project, and that such an occurrence does not necessarily reflect adversely on either the adequacy of the floor's design or the quality of its construction (Ytterberg 1987).

This guide describes how to produce high-quality concrete slabs-on-ground and suspended floors for various classes of service. It emphasizes such aspects of construction as site preparation, concrete materials, concrete mixture proportions, concrete workmanship, joint construction, load transfer across joints, form stripping procedures, finishing methods, and curing. Flatness/levelness requirements and measurements are outlined. A thorough preconstruction meeting is critical to facilitate communication among key participants and to clearly establish expectations and procedures that will be employed during construction to achieve the floor qualities required by the project specifications. Adequate supervision and inspection are required for job operations, particularly those of finishing.

Keywords: admixture; aggregate; consolidation; contract documents; curing; curling; deflection; durability; form; fracture; joint; mixture proportioning; placing; quality control; slab-on-ground; slabs; slump test.

CONTENTS

CHAPTER 1—INTRODUCTION, p. 3

- 1.1—Purpose, p. 3
- 1.2—Scope, p. 3

CHAPTER 2—DEFINITIONS, p. 3

CHAPTER 3—PREBID AND PRECONSTRUCTION MEETINGS, p. 3

- 3.1—Prebid meeting, p. 3
- 3.2—Preconstruction meeting, p. 3

ACI Committee Reports, Guides, and Commentaries are intended for guidance in planning, designing, executing, and inspecting construction. This document is intended for the use of individuals who are competent to evaluate the significance and limitations of its content and recommendations and who will accept responsibility for the application of the information it contains. ACI disclaims any and all responsibility for the stated principles. The Institute shall not be liable for any loss or damage arising there from.

Reference to this document shall not be made in contract documents. If items found in this document are desired by the Architect/ Engineer to be a part of the contract documents, they shall be restated in mandatory language for incorporation by the Architect/Engineer.

ACI 302.1R-15 supersedes ACI 302.1R-04 and was adopted and published June 2015. Copyright © 2015, American Concrete Institute.

All rights reserved including rights of reproduction and use in any form or by any means, including the making of copies by any photo process, or by electronic or mechanical device, printed, written, or oral, or recording for sound or visual reproduction or for use in any knowledge or retrieval system or device, unless permission in writing is obtained from the copyright proprietors.

CHAPTER 4—CLASSES OF FLOORS, p. 4

- 4.1—Classification of floors, p. 4
- 4.2—Single-course monolithic floors: Classes 1, 2, 4, 5, and 6, p. 4
- 4.3—Two-course floors: Classes 3, 7, and 8, p. 4
- 4.4—Class 9 floors, p. 6
- 4.5—Special finish floors, p. 6

CHAPTER 5—DESIGN CONSIDERATIONS, p. 6

- 5.1—Scope, p. 6
- 5.2—Slabs-on-ground, p. 6
- 5.3—Suspended slabs, p. 11
- 5.4—Miscellaneous details, p. 13

CHAPTER 6—SITE PREPARATION AND PLACING ENVIRONMENT, p. 14

- 6.1—Soil-support system preparation, p. 14
- 6.2—Suspended slabs, p. 16
- 6.3—Bulkheads, p. 16
- 6.4—Setting screed guides, p. 16
- 6.5—Installation of auxiliary materials, p. 16
- 6.6—Concrete placement conditions, p. 16

CHAPTER 7—ASSOCIATED MATERIALS, p. 17

- 7.1—Introduction, p. 17
- 7.2—Reinforcement, p. 17
- 7.3—Special-purpose aggregates, p. 18
- 7.4—Monomolecular films, p. 18
- 7.5—Curing materials, p. 18
- 7.6—Gloss-imparting waxes, p. 19
- 7.7—Liquid surface treatments, p. 19
- 7.8—Joint materials, p. 20
- 7.9—Volatile organic compounds (VOCs), p. 20

CHAPTER 8—CONCRETE MATERIALS AND MIXTURE PROPORTIONING, p. 20

- 8.1—Introduction, p. 20
- 8.2—Concrete, p. 20
- 8.3—Concrete properties, p. 20
- 8.4—Recommended concrete mixture, p. 21
- 8.5—Aggregates, p. 23
- 8.6—Portland cement, p. 24
- 8.7—Water, p. 25
- 8.8—Admixtures, p. 25
- 8.9—Concrete mixture analysis, p. 27

CHAPTER 9—BATCHING, MIXING, AND TRANSPORTING, p. 31

- 9.1—Batching, p. 31
- 9.2—Mixing, p. 32
- 9.3—Transporting, p. 32

CHAPTER 10—PLACING, CONSOLIDATING, AND FINISHING, p. 33

- 10.1—Placing operations, p. 33
- 10.2—Tools for spreading, consolidating, and finishing, p. 34

10.3—Spreading, consolidating, and finishing operations, p. 37

10.4—Finishing Class 1, 2, and 3 floors, p. 44

10.5—Finishing Class 4 and 5 floors, p. 44

10.6—Finishing Class 6 floors and monolithic-surface treatments for wear resistance, p. 44

10.7—Finishing Class 7 floors, p. 46

10.8—Finishing Class 8 floors (two-course unbonded), p. 47

10.9—Finishing Class 9 floors, p. 47

10.10—Toppings for precast floors, p. 48

10.11—Finishing lightweight concrete, p. 48

10.12—Non-slip floors, p. 50

10.13—Decorative and non-slip treatments, p. 50

10.14—Grinding as repair procedure, p. 52

10.15—Floor flatness and levelness, p. 52

10.16—Treatment when bleeding is a problem, p. 56

10.17—Delays in cold-weather finishing, p. 57

CHAPTER 11—CURING, PROTECTION, AND JOINT FILLING, p. 57

- 11.1—Purpose of curing, p. 57
- 11.2—Methods of curing, p. 57
- 11.3—Curing at joints, p. 58
- 11.4—Curing special concrete, p. 58
- 11.5—Length of curing, p. 59
- 11.6—Preventing plastic shrinkage cracking, p. 59
- 11.7—Curing after grinding, p. 59
- 11.8—Protection of slab during construction, p. 59
- 11.9—Temperature drawdown in cold storage and freezer rooms, p. 59
- 11.10—Joint filling and sealing, p. 60

CHAPTER 12—QUALITY CONTROL CHECKLIST, p. 60

- 12.1—Introduction, p. 60
- 12.2—Partial list of important items to be observed, p. 60

CHAPTER 13—CAUSES OF FLOOR AND SLAB SURFACE IMPERFECTIONS, p. 61

- 13.1—Introduction, p. 61
- 13.2—Random cracking, p. 62
- 13.3—Low wear resistance, p. 65
- 13.4—Dusting, p. 65
- 13.5—Scaling, p. 66
- 13.6—Popouts, p. 67
- 13.7—Blisters and delamination, p. 68
- 13.8—Spalling, p. 69
- 13.9—Discoloration, p. 70
- 13.10—Low spots and poor drainage, p. 71
- 13.11—Slab edge curling, p. 71
- 13.12—Evaluation of slab surface imperfections, p. 73

CHAPTER 14—REFERENCES, p. 73

Authored documents, p. 75

CHAPTER 1—INTRODUCTION

1.1—Purpose

This guide presents information relative to the construction of slab-on-ground and suspended-slab floors for industrial, commercial, and institutional buildings. It is applicable to the construction of normalweight and structural lightweight concrete floors and slabs made with conventional portland and blended cements. This guide identifies the various classes of floors based on use, construction design details, necessary site preparation, concrete type, and other related materials. In general, characteristics of the concrete slab surface and joint performance have a powerful impact on the serviceability of floors and other slabs. Because the eventual success of a concrete floor installation depends on the mixture proportions and floor finishing techniques used, considerable attention is given to critical aspects of achieving the desired finishes and the required floor surface tolerances.

1.2—Scope

This guide emphasizes choosing and proportioning of materials, design details, proper construction methods, and workmanship. Slabs specifically intended for the containment of liquids are beyond the scope of this guide. Whereas this guide does provide a reasonable overview of concrete floor construction, each project is unique and circumstances can dictate departures from the recommendations given in this guide. Contractors and suppliers should, therefore, thoroughly review contract documents before bid preparation (Chapter 3).

CHAPTER 2—DEFINITIONS

ACI provides a comprehensive list of definitions through an online resource, “ACI Concrete Terminology,” <http://www.concrete.org/store/productdetail.aspx?ItemID=CT13>. Definitions provided herein complement that resource.

differential set time—difference in timing from initial introduction of water to concrete mixture at batch plant to initial power floating.

dry-shake—dry mixture of hydraulic cement and fine aggregate (either mineral or metallic) that is distributed evenly over the surface of concrete flatwork and worked into the surface before time of final setting and then floated and troweled to desired finish.

mixture optimization indicator—intersection of the coarseness factor value and the workability factor on the coarseness factor chart.

rutting—creation of troughs in the soil support system in response to applied wheel loads.

score—creation of lines or notches in the surface of a concrete slab.

soil pumping—vertical displacement and rebound of the soil support system in response to applied moving loads.

water slump—magnitude of slump, measured in accordance with **ASTM C143/C143M**, which is directly attributed to the amount of water in the concrete mixture.

window of finishability—time period available for finishing operations after the concrete has been placed, consolidated, and struck-off, and before final troweling.

workability factor—percentage of combined aggregate that passes the No. 8 (2.36 mm) sieve.

CHAPTER 3—PREBID AND PRECONSTRUCTION MEETINGS

3.1—Prebid meeting

The best forum for a thorough review of contract documents before the bid preparation is a prebid meeting. This meeting offers bidders an opportunity to ask questions and to clarify their understanding of contract documents before submitting their bids. A prebid meeting also provides the owner and the owner’s slab designer an opportunity to clarify intent where documents are unclear and to respond to last-minute questions in a manner that provides bidders an opportunity to be equally responsive to the contract documents.

3.2—Preconstruction meeting

Successful construction of slabs-on-ground or suspended floors or slabs involves the coordinated efforts of many subcontractors and material suppliers. The slab designer should schedule a preconstruction meeting to establish and coordinate procedures that will enable key participants to produce the best possible product under the anticipated field conditions. This meeting should be attended by responsible representatives of organizations and material suppliers directly involved with either the design or construction of floors.

3.2.1 Agenda items—The preconstruction meeting should confirm and document the responsibilities and anticipated interaction of key participants involved in slab-on-ground or suspended floor or slab construction. Following is a list of agenda items appropriate for such a meeting, including ones for which the contract documents should establish a clear responsibility. The following list is not all-inclusive:

- a) Site preparation
- b) Grades for drainage, if any
- c) Work associated with installation of auxiliary materials, such as vapor barriers, vapor retarder/barriers, edge insulation, electrical conduit, mechanical sleeves, drains, and embedded plates
- d) Class of floor
- e) Floor thickness
- f) Reinforcement, when required
- g) Construction tolerances: base (rough and fine grading), forms, slab thickness, surface configuration, and floor flatness and levelness requirements (including how and when measured)
- h) Joints and load-transfer mechanism
- i) Materials: cements, fine aggregate, coarse aggregate, water, and admixtures (usually by reference to applicable ASTM standards)
- j) Special aggregates, admixtures, or monolithic surface treatments, where applicable
- k) Concrete specifications including:
 - 1) Compressive strength, flexural strength, or both
 - 2) Recommended cementitious material content, if applicable
 - 3) Maximum size, grading, and type of coarse aggregate