



**Prefabricated concrete elements**  
**Part 2: Building construction**



This Australian Standard® was prepared by Committee BD-066, Tilt-up construction. It was approved on behalf of the Council of Standards Australia on 8 July 2015. This Standard was published on 3 September 2015.

---

The following are represented on Committee BD-066:

- Australasian Fire and Emergency Service Authorities Council
  - Australian Council of Trade Unions
  - Australian Engineered Fasteners and Anchors Council
  - Australian Institute of Building Surveyors
  - Australian Steel Institute
  - Building Designers Association of NSW
  - Cement Concrete and Aggregates Australia
  - Concrete Institute of Australia
  - Concrete Pipe Association of Australasia
  - Crane Industry Council of Australia
  - Curtin University of Technology
  - Engineers Australia
  - Master Builders Australia
  - National Association of Testing Authorities Australia
  - National Precast Concrete Association Australia
  - Steel Reinforcement Institute of Australia
  - Sydney University
  - WorkCover New South Wales
  - WorkSafe Victoria
- 

This Standard was issued in draft form for comment as DR2 AS 3850.2.

Standards Australia wishes to acknowledge the participation of the expert individuals that contributed to the development of this Standard through their representation on the Committee and through the public comment period.

---

### **Keeping Standards up-to-date**

Australian Standards® are living documents that reflect progress in science, technology and systems. To maintain their currency, all Standards are periodically reviewed, and new editions are published. Between editions, amendments may be issued.

Standards may also be withdrawn. It is important that readers assure themselves they are using a current Standard, which should include any amendments that may have been published since the Standard was published.

Detailed information about Australian Standards, drafts, amendments and new projects can be found by visiting [www.standards.org.au](http://www.standards.org.au)

Standards Australia welcomes suggestions for improvements, and encourages readers to notify us immediately of any apparent inaccuracies or ambiguities. Contact us via email at [mail@standards.org.au](mailto:mail@standards.org.au), or write to Standards Australia, GPO Box 476, Sydney, NSW 2001.

---

Australian Standard®

## Prefabricated concrete elements

### Part 2: Building construction

First published as AS 3850.1—1990, AS 3850.2—1990 and AS 3850.3—1992.  
AS 3850.1—1990, AS 3850.2—1990 and AS 3850.3—1992 revised,  
amalgamated and redesignated as AS 3850—2003.  
AS 3850—2003 revised and redesignated (in part) as AS 2380.2:2015.  
Reissued incorporating Amendment No. 1 (December 2018).

#### **COPYRIGHT**

© Standards Australia Limited

All rights are reserved. No part of this work may be reproduced or copied in any form or by any means, electronic or mechanical, including photocopying, without the written permission of the publisher, unless otherwise permitted under the Copyright Act 1968.

Published by SAI Global Limited under licence from Standards Australia Limited, GPO Box 476, Sydney, NSW 2001, Australia

ISBN 978 1 76035 243 1

## PREFACE

This Standard was prepared by the Standards Australia Committee BD-066, Tilt-up Construction, to supersede AS 3850—2003, *Tilt-up concrete construction*.

*This Standard incorporates Amendment No. 1 (December 2018). The changes required by the Amendment are indicated in the text by a marginal bar and amendment number against the clause, note, table, figure or part thereof affected.*

This Standard is part of a series, which comprises the following parts:

AS

3850 Prefabricated concrete elements

3850.1 Part 1: General requirements

3850.2 Part 2: Building construction (this Standard)

The objective of this part of the Standard is to provide requirements for planning, construction, design, casting, transportation, erection and incorporation into the final structure of prefabricated concrete elements in building construction.

In this Standard where the word ‘shall’ is used, a mandatory requirement is implied; where the word ‘should’ is used, a recommendation is implied.

Statements expressed in mandatory terms in notes to tables are deemed to be requirements of this Standard.

The term ‘normative’ has been used in this Standard to define the application of the appendix to which it applies. A ‘normative’ appendix is an integral part of a Standard.

*This document includes commentary on some of the clauses, tables and figures of the Standard. The commentary directly follows the relevant clause, table or figure, is designated by ‘C’ preceding the clause number and is printed in italics in a box. The commentary is for information and guidance and does not form part of the Standard.*

## CONTENTS

	<i>Page</i>
SECTION 1 SCOPE AND GENERAL	
1.1 SCOPE.....	5
1.2 NORMATIVE REFERENCES .....	5
SECTION 2 DESIGN AND DOCUMENTATION	
2.1 GENERAL.....	6
2.2 DESIGN STAGES .....	6
2.3 ERECTION DESIGN .....	6
2.4 BUILDING STABILITY DURING ERECTION AND CONSTRUCTION .....	7
2.5 DESIGN FOR MANUFACTURE, HANDLING AND ERECTION.....	8
2.6 JOINT WIDTHS .....	33
2.7 FOOTINGS.....	34
2.8 CONNECTIONS .....	35
2.9 STRONGBACKS .....	37
2.10 DOCUMENTATION.....	38
2.11 TOLERANCES.....	39
SECTION 3 CASTING	
3.1 GENERAL.....	44
3.2 LAYOUT .....	44
3.3 CASTING BED .....	44
3.4 SURFACE FINISH AND FORMWORK.....	44
3.5 CURING AND RELEASE AGENTS .....	44
3.6 LIFTING, BRACE AND FIXING INSERTS .....	45
3.7 WELDING.....	45
3.8 IDENTIFICATION AND ORIENTATION .....	45
3.9 INSPECTION .....	45
3.10 COMPACTION OF CONCRETE.....	46
3.11 ELEMENT RELEASE (LIFT-OFF FROM CASTING BED).....	46
SECTION 4 TRANSPORT, CRANAGE AND ERECTION	
4.1 TRANSPORT .....	47
4.2 STORAGE AND MULTIPLE HANDLING.....	49
4.3 CRANES AND RIGGING.....	49
4.4 ERECTION.....	51
4.5 DAMAGE AND REPAIR.....	56
SECTION 5 TEMPORARY SUPPORTS	
5.1 INSTALLATION AND INSPECTION OF TEMPORARY BRACING AND PROPPING.....	57
5.2 SUPERIMPOSED LOADS.....	57
5.3 LEVELLING PADS AND SHIMS .....	57
5.4 GROUTING OF THE BASE .....	58
SECTION 6 INCORPORATION INTO FINAL STRUCTURE	
6.1 FIXING TO FINAL STRUCTURE .....	59
6.2 INSPECTION AND REMOVAL OF TEMPORARY SUPPORTS.....	59

	<i>Page</i>
APPENDIX A INFORMATION REQUIRED IN DOCUMENTATIONS.....	60
BIBLIOGRAPHY .....	63

STANDARDS AUSTRALIA

---

**Australian Standard**

**Prefabricated concrete elements**

---

Part 2: Building construction

---

SECTION 1 SCOPE AND GENERAL

**1.1 SCOPE**

This Standard provides requirements for planning, construction, design, casting, transportation, erection and incorporation into the final structure of prefabricated concrete elements in building construction. It applies to prefabricated concrete elements including, but not limited to, wall elements, columns, beams, flooring and facade elements used in building construction.

This Standard does not cover the following elements:

- (a) Concrete pipes, bridge beams or culverts (e.g. concrete pipes or culverts used in civil construction works to channel water under roads, railways or embankments).
- (b) Small individual concrete elements that can be handled manually (e.g. bricks, blocks and pavers).

NOTE: The elements mentioned in Items (a) and (b) are covered by other Australian Standards.

**1.2 NORMATIVE REFERENCES**

The following are the normative documents referenced in this Standard:

NOTE: Documents referenced for informative purposes are listed in the Bibliography.

AS	
2550	Cranes, hoists and winches—Safe use (series)
3610	Formwork for concrete
3610.1	Part 1: Documentation and surface finish
3850	Prefabricated concrete elements
3850.1	Part 1: General requirements
4100	Steel structures
AS/NZS	
1100	Technical drawing
1100.501	Part 501: Structural engineering drawing
1170	Structural design actions
1170.0	Part 0: General principles
1170.2:2011	Part 2: Wind actions
1554	Structural steel welding
1554.3	Part 3: Welding of reinforcing steel